



## NOTES:

1. BEDDING FROM 4" BELOW BOTTOM OF THE SERVICE LINE TO 12" OVER THE TOP OF PIPE SHALL BE 3/8" WASHED ROCK CHIPS (MAG LOW VOLUME CHIPS).
2. UNDER OR WITHIN 2' OF AC, BACKFILL AND REPLACE PAVEMENT PER CITY OF APACHE JUNCTION DETAIL 200M. ELSEWHERE, BACKFILL WITH COMPACTED SCREENED NATIVE MATERIAL.
3. DETECTABLE LOCATION DEVICE SHALL CONSIST OF EITHER:
  - METALLIC WARNING TAPE APPROXIMATELY 2' BELOW SURFACE (SEWER MAIN)
  - SEWER TRACER WIRE PLACED ON PIPE (SERVICE LINE)