



## NOTES:

1. BEDDING FROM 4" BELOW BOTTOM OF THE SEWER MAIN TO 12" OVER THE TOP OF PIPE SHALL BE  $3/8"$  WASHED ROCK CHIPS (MAG LOW VOLUME CHIPS).
2. UNDER OR WITHIN 2' OF AC, BACKFILL AND REPLACE PAVEMENT PER CITY OF APACHE JUNCTION DETAIL 200M. ELSEWHERE, BACKFILL WITH COMPACTED AGGREGATE BASE OR, WITH PRIOR DISTRICT APPROVAL, COMPACTED SCREENED NATIVE MATERIAL.
3. METALLIC WARNING TAPE APPROXIMATELY 2' BELOW SURFACE.



**APACHE JUNCTION  
SEWER DISTRICT**

RECLAIMING WATER FOR THE FUTURE

BEDDING, BACKFILL, AND COMPACTION

REVISED  
JUL-15-2024

DETAIL NO.  
AJS200